

# ***Bridgeton Landfill, LLC***

## **WEEKLY PROJECT UPDATE: PROGRESS ON EVOH LINER AND LEACHATE TANK CONSTRUCTION; SUMP MAINTENANCE SCHEDULED**

**BRIDGETON, MO (October 4, 2013)** – The Bridgeton Landfill, LLC project team announced today that it has installed approximately five acres of the advanced ethylene vinyl alcohol (EVOH) liner system in the South Quarry and that construction on the four leachate tank floors for the pre-treatment system was completed this week.

The team is more than halfway finished with installing the expansion of its advanced EVOH liner system in the South Quarry, as approximately 5 acres of the 7.5-acre expansion project is now completed. When the expansion of the EVOH system is finished, it will cover approximately 42 acres, including the entire South Quarry waste mass and surrounding land on each side. The EVOH system, which consists of two layers of High Density Polyethylene (HDPE) liner with a layer of EVOH in the middle, is more effective at controlling odors than the previous HDPE flexible liner.

Today, the team is conducting maintenance on a perimeter sump in the southwest corner of the South Quarry. As a result of this work, a small portion of the EVOH cap will be opened and we may need to conduct minor excavation work. It is anticipated that work on the sump will take several hours to complete and may cause temporary off-site detection of odor.

Bridgeton Landfill also submitted its weekly and monthly report to the Missouri Department of Natural Resources (MDNR). This information was posted on the landfill's website, [www.BridgetonLandfill.com](http://www.BridgetonLandfill.com).

Next week, Bridgeton Landfill will continue work on the EVOH system expansion as well as the installation of bases and tanks for the four (4), one-million gallon tanks that are part of the planned leachate pre-treatment system.

###